

INSTALLATION INSTRUCTIONS

69RT/ 71CD SPILL CONTAINMENT

Read these installation instructions completely and carefully before installation. The Universal 69RT/71CD comes pre-assembled for easy installation.

Before installing the 69RT/71CD containment manhole, coat both the male and female threads with a non-hardening pipe dope that is compatible with the product to be contained.

Install the 69RT/71CD by threading onto the tank riser until it is hand tight.

To finish tightening the unit, place a pipe wrench on the bottom external hex and tighten.

The top edge should be positioned a minimum of 2" above the final grade level to provide adequate slope for drainage. (See API recommended practices 1615)

NOTE: Every unit should be tested for leaks before and after installation. Fill the unit completely with water. If the water level drops within one hour, then a leak exists. Check the drain valve for proper seating and re-test. If the unit continues to leak, then replace the entire unit with another and re-test. After the concrete has been poured, re-test the unit to make sure no damage occurred during installation.

The unit should be tested and inspected every 6 months or more frequently if you are a high volume user or if conditions warrant. Damaged or leaking units should be replaced immediately.

Proven Performance



UNIVERSAL VALVE CO., INC.

478 Schiller Street • Elizabeth, New Jersey 07206

e-mail: sales@universalvalve.com

visit us at: www.universalvalve.com

